123 River Street


Exampleville, Ohio 43702

Owner Example, Pat
NFIP Community 399990 Exampleville, City of
Date of Assessment 09/21/2026

Percent Damaged

75.0%

Substantially Damaged



Basis for Value of Structure
$129,189.26
Computed Actual Cash Value

Basis for Cost of Repairs
$96,900.46
Computed Damages

Structure Address

Owner's Name	Example, Pat
Street Address	123 River Street
City	Exampleville
County/Parish	Union
State	Ohio
Zip	43702
Phone	(555) 555-0142

Subdivision

Subdivision	Riverside Addition
Parcel #	092-0004-0118-00
Lot #	18
Elev. of Lowest Floor	486.5 ft.
Datum	NAVD 88

Structure Information

Year of Construction	1962
Residence Type	Single Family Residence
Quality	Good

Community

NFIP Community Name	Exampleville, City of
NFIP Community ID #	399990
Latitude	39.098712
Longitude	-84.507634

Damage Information

Date of Assessment	09/21/2026	Date of Damage	09/14/2026
Inspector Name	Inspector A	Cause of Damage	Flood
Inspector Phone	(555) 555-0100	Duration of Flood	2 Days
Residence Information	Brick ranch, attached one-car garage.	Est. Depth of Flood Above Lowest Floor	4.25

NFIP Information

Firm Panel #	Suffix	Date of FIRM Panel	Firm Zone	BFE	Regulatory Floodway
39061C0232	E	09/17/2010	AE	489.25	No

Damage Summary

Replacement Cost	$170,434.38	Computed Damages	$96,900.46
Depreciation %	24.2%	Percent of Existing Improvements and Repairs Pre-Disaster	
Computed Actual Cash Value*	$129,189.26	Repair/Reconstruction %	75.0%
Other Depreciation Explanation			

* Per FEMA Publication 213, Actual Cash Value may be used as Market Value.

Optional User Entered Data

Professional Market Appraisal	Contractor Estimate
Tax Assessed Value	Community Estimate
Factor Adjustment	
Adjusted Tax Assessed Value	

Authorized Local Official : _____
Signature


Authorized Local Official : _____
Printed Name

400 Front Street

Exampleville, Ohio 43702-1234

Owner Riverside Holdings LLC
NFIP Community 399990 Exampleville, City of
Date of Assessment 09/22/2026

Percent Damaged
51.6%
Substantially Damaged



Basis for Value of Structure
$1,271,911.80
Computed Actual Cash Value

Basis for Cost of Repairs
$656,876.72
Computed Damages

Structure Address

Owner's Name	Riverside Holdings LLC
Street Address	400 Front Street
City	Exampleville
County/Parish	Union
State	Ohio
Zip	43702-1234
Phone	

Subdivision

Subdivision	
Parcel #	
Lot #	
Elev. of Lowest Floor	
Datum	

Structure Information

Year of Construction	1978
Use	Office Building
Quality	Good

Community

NFIP Community Name	Exampleville, City of
NFIP Community ID #	399990
Latitude	
Longitude	

Damage Information

Date of Assessment	09/22/2026	Date of Damage	09/14/2026
Inspector Name	R. Inspector	Cause of Damage	Flood
Inspector Phone		Duration of Flood	3 Days
Structure Information	Three-story steel frame office.	Est. Depth of Flood Above Lowest Floor	2.50

NFIP Information

Firm Panel #	Suffix	Date of FIRM Panel	Firm Zone	BFE	Regulatory Floodway

Damage Summary

Replacement Cost	$1,851,400.00	Computed Damages	$656,876.72
Depreciation %	31.3%	Percent of Existing Improvements and Repairs Pre-Disaster	
Computed Actual Cash Value*	$1,271,911.80	Repair/Reconstruction %	51.6%
Other Depreciation Explanation			

* Per FEMA Publication 213, Actual Cash Value may be used as Market Value.

Optional User Entered Data

Professional Market Appraisal	Contractor Estimate
Tax Assessed Value	Community Estimate
Factor Adjustment	
Adjusted Tax Assessed Value	

Authorized Local Official : _____
Signature


Authorized Local Official : _____
Printed Name

18 Mill Creek Street

Exampleville, Ohio 43702

Owner Rivera, Jordan
NFIP Community 399991 Union County Unincorporated Areas
Date of Assessment 09/23/2026

Percent Damaged
32.1%
Not Substantially Damaged



Basis for Value of Structure
$129,189.26
Computed Actual Cash Value

Basis for Cost of Repairs
$41,449.64
Computed Damages

Structure Address

Owner's Name	Rivera, Jordan
Street Address	18 Mill Creek Street
City	Exampleville
County/Parish	Union
State	Ohio
Zip	43702
Phone	

Subdivision

Subdivision	
Parcel #	
Lot #	
Elev. of Lowest Floor	
Datum	

Structure Information

Year of Construction	1962
Residence Type	Single Family Residence
Quality	Good

Community

NFIP Community Name	Union County Unincorporated Areas
NFIP Community ID #	399991
Latitude	
Longitude	

Damage Information

Date of Assessment	09/23/2026	Date of Damage	09/14/2026
Inspector Name	Inspector A	Cause of Damage	Flood
Inspector Phone		Duration of Flood	2 Days
Residence Information		Est. Depth of Flood Above Lowest Floor	

NFIP Information

Firm Panel #	Suffix	Date of FIRM Panel	Firm Zone	BFE	Regulatory Floodway

Damage Summary

Replacement Cost	$170,434.38	Computed Damages	$41,449.64
Depreciation %	24.2%	Percent of Existing Improvements and Repairs Pre-Disaster	
Computed Actual Cash Value*	$129,189.26	Repair/Reconstruction %	32.1%
Other Depreciation Explanation			

* Per FEMA Publication 213, Actual Cash Value may be used as Market Value.

Optional User Entered Data

Professional Market Appraisal	Contractor Estimate
Tax Assessed Value	Community Estimate
Factor Adjustment	
Adjusted Tax Assessed Value	

Authorized Local Official : _____
Signature

Authorized Local Official : _____
Printed Name

22 Mill Creek Street

Exampleville, Ohio 43702

Owner Lee, Sam
NFIP Community 399991 Union County Unincorporated Areas
Date of Assessment 11/11/2026

Percent Damaged
0.0%
Resident Refused Inspection

Basis for Value of Structure
Not Provided
Computed Actual Cash Value

Basis for Cost of Repairs
$0.00
Computed Damages

Structure Address

Owner's Name	Lee, Sam
Street Address	22 Mill Creek Street
City	Exampleville
County/Parish	
State	Ohio
Zip	43702
Phone	

Subdivision

Subdivision	
Parcel #	
Lot #	
Elev. of Lowest Floor	
Datum	

Structure Information

Year of Construction	1962
Residence Type	Single Family Residence
Quality	Good

Community

NFIP Community Name	Union County Unincorporated Areas
NFIP Community ID #	399991
Latitude	
Longitude	

Damage Information

Date of Assessment	11/11/2026	Date of Damage	09/14/2026
Inspector Name	Inspector A	Cause of Damage	Flood
Inspector Phone		Duration of Flood	2 Days
Residence Information		Est. Depth of Flood Above Lowest Floor	

NFIP Information

Firm Panel #	Suffix	Date of FIRM Panel	Firm Zone	BFE	Regulatory Floodway

Damage Summary

Replacement Cost	$170,434.38	Computed Damages	$96,900.46
Depreciation %	24.2%	Percent of Existing Improvements and Repairs Pre-Disaster	
Computed Actual Cash Value*	$129,189.26	Repair/Reconstruction %	75.0%
Other Depreciation Explanation	Owner declined entry; exterior inspection only.		

* Per FEMA Publication 213, Actual Cash Value may be used as Market Value.

Optional User Entered Data

Professional Market Appraisal	Contractor Estimate
Tax Assessed Value	Community Estimate
Factor Adjustment	
Adjusted Tax Assessed Value	

Authorized Local Official : _____ Signature

Authorized Local Official : _____ Printed Name